

Attachment B: Schedule of Values

Description

1 Construction Water Trucks (price to include operator)

Provide hourly pricing for +/- 3,800 gallon water truck, including an experienced driver, to operate, off road, on a construction site as part of a grading/earthwork crew to provide dust control and water support, as necessary to make compaction. This is a multi-year project with ongoing work based on an as needed basis. Please review and confirm that you are able to meet and/or exceed the Subcontractor Insurance Requirements.

Water Truck & Operator	\$/Hour
Water Truck Size	Gallons
Quantity of Water Trucks Available	Each

2 Street Sweepers

Provide hourly pricing for a mechanical sweeper, including an experienced operator, to operate on a construction site as part of a grading/earthwork crew to mechanically sweep/clean streets of dirt tracked onto asphalt streets by construction vehicles entering and exiting the site. This is a multi-year project with ongoing work based on an as needed basis. Please review and confirm that you are able to meet and/or exceed the Subcontractor Insurance Requirements.

Street Sweeper & Operator	\$/Hour
Street Sweeper Size / Type	
Quantity of Sweepers Available	Each

3 Site Security

Provide hourly pricing for a site security guard to observe a construction site and construction equipment during off hours (nights and weekends) to ensure the safety of the materials, equipment and site. Security guard pricing needs to include transportation so that security guard can travel the site during the work shift. This is a multi-year project with ongoing work based on an as needed basis. Please review and confirm that you are able to meet and/or exceed the Subcontractor Insurance Requirements.

Please provide written proposal and pricing

4 Temporary Sanitary Facilities

Provide monthly rental pricing for temporary sanitary facilities (restrooms and hand washing stations), including frequency of servicing these facilities for an ongoing construction site. This is a multi-year project with ongoing work based on an as needed basis. Please review and confirm that you are able to meet and/or exceed the Subcontractor Insurance Requirements.

Temporary Sanitary Facility & Service	\$/Month
Quantity of Units Available	Each
Temporary Hand Wash Facility & Service	\$/Month
Quantity of Units Available	Each

5 Construction Hauling (price to include driver)

Provide hourly pricing for trucking (construction hauling), including driver, to operate on a construction site as part of a grading/earthwork crew to import construction materials from commercial asphalt and rock plants as well as onsite hauling of soil and rock. Please provide hourly pricing along with the number of each type of truck available. This is a multi-year project with ongoing work based on an as needed basis. Please review and confirm that you are able to meet and/or exceed the Subcontractor Insurance Requirements.

Double Bottom Dump Truck	\$/Hour
Quantity of BD Trucks Available	Each
10 Wheeler Dump Truck	\$/Hour
Quantity of 10 W. Dump Trucks Available	Each
Super 10 Dump Truck	\$/Hour
Quantity of Super Dump Trucks Available	Each
Semi-End Dump - Dump Truck	\$/Hour
Quantity of Semi-End Dump Trucks Available	Each

6 Storm Drain Video Inspection

Provide storm drain video inspections and recordings of existing storm drain facilities located on/or adjacent to an active construction site. Please provide information as to size (smallest and largest) of storm drain pipe that can be video inspected. This is a multi-year project with ongoing work based on an as needed basis. Please review and confirm that you are able to meet and/or exceed the Subcontractor Insurance Requirements.

Please provide written proposal and pricing

7 Hydroseeding (Specification Section 329500)

Provide Hydroseeding and/or Tack and Mulch of drainage swales, slopes and flat areas on an active construction site. All Hydroseeding and Tack and Mulch needs to be provided in accordance with Specification Section 329500 "Hydroseeding" as detailed in the Specifications in the drop box link. This is a multi-year project with ongoing work based on an as needed basis, which will require multiple mobilizations for this scope of work. Please review and confirm that you are able to meet and/or exceed the Subcontractor Insurance Requirements.

Spec. Section 329500 Hydroseeding		
Area 1 - sides of swale	\$/SF	31,500 SF
Area 2 - bottom of swale	\$/SF	59,700 SF
Area 3 - disturbed areas at swale	\$/SF	30,000 SF
Tack & Mulch Outfall Surcharge	\$/SF	257,500 SF
Tack & Mulch South Surcharge	\$/SF	554,580 SF
Quantity able to perform per mobilization		
Cost per Mobilization	\$/EA	4 EA

8 Temporary Construction Fencing & Gates

Provide pricing for temporary construction fencing and gates for an active construction site. Temporary fencing is to be 6' high, driven post, temporary fence. All posts are to be 1-5/8" x 8' tall driven at 10' on center at 2' deep with 2-3/8" by 11-1/2 gauge x 6' tall chain link fence fabric connected to the posts. Gates are to be 6' tall x 30' wide double swing gates with the posts set in concrete. This is an install only price. This is a multi-year project with ongoing work based on an as needed basis. Please review and confirm that you are able to meet and/or exceed the Subcontractor Insurance Requirements.

Furnish & Install 6' high driven post temporary fence. All posts 1-5/8" x 8' driven at 10' on center, 2' deep. 2-3/8" x 11-1/2 gauge x 6' high chain link fabric tied to posts. No bracing or tension wire.	\$/LF	13,000 LF
Furnish & Install 6' x 30' double swing gates with all posts set in concrete.	\$/EA	6